


INDIVIDUAL PIECE ELEVATIONS

E



C-SHAPE - FRONT ELEVATION


C-SHAPE - TYP. SIDE ELEVATION

LL SHAPE RIGHT ELEVATION

D

INDIVIDUAL PIECE FLOOR PLANS

C



L-SHAPE - FLOOR PLAN

C-SHAPE - FLOOR PLAN

GRINDING BOOTH GENERAL NOTES

1. THERE MUST BE ONE SECTION OF FOUR BOOTHS.
2. THERE MUST BE NO MORE THAN ONE NON-WELDED JOINT PER BOOTH OR NO MORE THAN THREE NON-WELDED JOINTS PER SECTION OF FOUR BOOTHS. ALL TABLETOPS AND SHELVES MUST BE WELDED TO THE PANELS. THE RECOMMENDED WAY TO ACHIEVE THIS WOULD BE TO FABRICATE THREE 'L-SHAPED' PANELS AND ONE 'C-SHAPED' PANEL FOR EACH FOUR-BOOTH SECTION. THIS WOULD LEAVE A NON-WELDED JOINT AT THE CORNER OF THE REAR WALL IN EACH BOOTH. DIMENSIONS WILL STILL BE REQUIRED TO MEET THE SPECIFICATIONS ON THE PRINT. FURTHERMORE, THERE MUST BE NO BOLTS OR FASTENERS EXTENDING OUT OF THE REAR OF THE BOOTH.
3. ALL WELDS MUST MEET THE VISUAL INSPECTION REQUIREMENTS OF THE AMERICAN WELDING SOCIETY D1.1 STRUCTURAL STEEL WELDING CODE AND MUST BE INSPECTED PRIOR TO APPLYING THE POWDER COAT FINISH. BUYER WILL SUPPLY THE CERTIFIED WELDING INSPECTOR AND MUST BE NOTIFIED 48 HOURS PRIOR TO INSPECTION. IT IS THE VENDOR'S RESPONSIBILITY TO CONTRACT THE BUYER AT THIS TIME.
4. THERE MUST BE INCLUDED A WAY TO LEVEL BOOTHS BY EITHER A SLOTTED ATTACHMENT AT THE POINT WHERE THE TWO PANELS JOIN, OR BY LEVELING ADJUSTMENTS ON THE BOTTOM OF EACH FOOT, OR BOTH. ALL POINTS WHERE THE TUBING EXTENDS TO THE FLOOR MUST MAKE FULL CONTACT WITH FLOOR PRIOR TO ANCHORING.
5. WITH THE EXCEPTION OF THE 3/8" TABLETOP, ALL PARTS ARE TO BE POWDER COATED (COLOR SHALL MATCH SHERWIN WILLIAMS 7018 DOVETAIL) PRIOR TO INSTALLATION. THERE SHALL BE NO WELDING, GRINDING, OR CUTTING AFTER THE POWDER COATING IS APPLIED. THEREFORE, THERE SHOULD BE NO TOUCH-UP REQUIRED.
6. THERE SHALL BE NO HOLES IN ANY PARTS THAT ARE LEFT OPEN AFTER THE INSTALLATION IS COMPLETE. ANY OPENINGS AT THE END OF THE PIPE OR TUBING SHOULD BE PERMANENTLY CAPPED PRIOR TO POWDER COAT APPLICATION.

GRINDING BOOTH SIZES & THICKNESS


- A. LEGS & BRACING IN PANELS = 2.0"x2.0"x1/8" SQUARE TUBE
- B. WALL PANELS BETWEEN BRACING & LEGS = .125" SHEET
- C. TABLETOP = .375" PLATE

GRINDING BOOTH QUANTITY

- QUANTITY PER ASSEMBLY OF 4
- A. L-SHAPE - 3 PIECES
 - B. C-SHAPE - 1 PIECE

ASSEMBLED BOOTH DRAWINGS - FOR REFERENCE ONLY. SEE TO INDIVIDUAL PIECES ABOVE FOR DIMENSIONS AND DETAILS

B



ASSEMBLED ELEVATION OF BOOTH REFER TO INDIVIDUAL PIECES FOR DIMENSIONS

ASSEMBLED SIDE ELEVATION OF BOOTH REFER TO INDIVIDUAL PIECES FOR DIMENSIONS

ASSEMBLED FLOOR PLAN OF BOOTH REFER TO INDIVIDUAL PIECES FOR DIMENSIONS

STATE PROJECT #: H59-6081-JM



CHEROKEE ADVANCED TECHNOLOGY CENTER CONSTRUCTION



110 WEST NORTH STREET SUITE 300 GREENVILLE, SOUTH CAROLINA 29601 TEL. 864.235.0405 FAX 864.233.4027



MEMBERS OF THE AMERICAN INSTITUTE OF ARCHITECTS

COPYRIGHT 2014 ALL RIGHTS RESERVED PRINTED OR ELECTRONIC DRAWINGS AND DOCUMENTATION MAY NOT BE REPRODUCED IN ANY FORM WITHOUT WRITTEN PERMISSION FROM LS3P ASSOCIATES LTD.

REVISIONS:

No.	Description	Date
2	ISSUE FOR BID	09-12-2014
3	ISSUE FOR BID, REVISED	10-28-2014

PROJECT: 3202-131890
DATE: 10/28/2014
DRAWN BY: WBH
CHECKED BY: CRS

GRINDING BOOTH DIMENSIONS & DETAILS

AO-004